

Intelligent
HARDWARE

GRIDLOCK[®]
SECURITY PRODUCTS
Multi-point locking systems

Security door furniture
& Security cylinders



GRID
LOCK

quickassemble


Patented Adjustable Hinges

Our unique 3 way adjustable hinge system offers the installer maximum flexibility during the installation process.

Hinge cradles are secured to the door frame with the corresponding hinge receivers fitted to the door leaf. Installation, or hanging of the door, is then carried out simply by "snapping" the door receivers onto the hinge jamb. Once in place the relative door position can then be adjusted to ensure an optimum fit within the doorframe.




- **Vertical adjustment** – allows the door to be moved up or down +/- 2.5mm
- **Horizontal adjustment** – allows the door to be moved left or right +/- 2.5mm
- **Lateral adjustment** – allows the door to be moved in or out of the doorframe rebate +/- 2.5mm
- **Available to suit:** 44mm & 34mm thick doors.
- **Tested to:** EN1935 CE Marked for FD30 fire doors.



Euro-Profile & Sever Secure Cylinders



- **BS EN 1303:2005 6 pin Euro Profile Cylinders.**
Tested to 100,000 cycles, Grade 6.
Key related security Grade 6.
Resistance to attack by drilling Grade 2.
- Minimum 150,000 lock differs.
- Available in Polished Brass and Satin Nickel finishes.
- Various sizes, single cylinders and thumb-turn versions to suit all multi-point locks in this range are available as special order on request.



Sever Secure Options

- Incorporates a sever-point for additional protection against cylinder attack.
- Anti-plug extraction pins.
- Withstood the cylinder attack test, included in PAS24 test (Nov 2005).

Sever Secure

Door Furniture

Sleeved Letterplates

- 290 x 65mm overall size.
- 180° opening letterflap.
- Available with or without internal brushes.

Finishes available:

- Silver Flap with Black Surround
- Gold Flap with Black Surround
- Evershine Brass Flap with Gold Surround
- Polished Stainless Steel Flap with Silver Surround
- Satin Stainless Steel Flap with Silver Surround

Security Chains

- Narrow and Standard design chains.

Finishes available:

- Brass Plated
- Polished Chrome Plated

Door Knockers

- 152mm URN type door knockers.

Finishes available:

- Evershine Brass
- Evershine Polished Chrome
- Evershine Satin Chrome

Viewers

- 180° viewing angle.

Finishes available:

- Brass Plated
- Polished Chrome Plated

Numerals

- 76mm face fixing.

Finishes available:

- Evershine Brass
- Evershine Chrome



Door Handle

Door Viewer

Door Numerals

Door Security Chains

Sleeved Letterplates

Door Knocker



GRIDLOCK®

E-Series

Multipoint Lock

- British designed to the latest European specifications.
- Passed the loading tests of PAS 24.
- Performed over 50,000 cycles.
- Successfully assessed in a fire resistant doorset to EN1634-1:2000 (30 minute).
- Patented 20mm bolt throw with lift lever action and one turn of the key (Pat 0322874.9).
- Adjustable metal box keeps.
- Lacquered forend in gold or silver.
- Designed to operate with standard or ~~Evershine~~ **Secure** cylinders giving extra protection against cylinder attack.
- Designed to operate with our 'Sienna' and 'Verona' door furniture, available in Evershine Polished Brass PVD or Evershine Polished & Satin Chrome PVD finishes. Guaranteed not to discolour for 25 years*. Also available in Black and White powder coated finishes to special order.

GRIDLOCK®
E-Series



ORDER DETAILS

Code	Finish
MPL.GRID.E.GA	Lacquered Gold
MPL.GRID.E.SI	Lacquered Silver

GRIDLOCK®

Lever Furniture

E Series Sienna

- The Sienna Euro lock furniture has been designed to function with the E-Series **GRIDLOCK** multi-point lock.
- It beautifully combines ergonomics with functionality and a streamlined, modern appearance.
- Available in Evershine Polished Brass PVD or Evershine Polished and Satin Chrome PVD finishes. Also available in a Powder Coated White finish.
- Guaranteed not to discolour for 25 years*.



Sienna
Euro lock
furniture

ORDER DETAILS

Code	Finish
SIE.02.ES	Evershine Brass
SIE.02.ESC	Evershine Chrome
SIE.02.ESSCP	Evershine Satin Chrome
SIE.02.WHT	White Powder Coated

E Series Verona

- The Verona Euro lock furniture has been designed to function with the E-Series **GRIDLOCK** multi-point lock.
- Inspired by fashion designers and architects, this furniture effortlessly reflects all that is contemporary.
- Available in Evershine Polished Brass PVD or Evershine Polished and Satin Chrome PVD finishes.
- Guaranteed not to discolour for 25 years*.



Verona
Euro lock
furniture

ORDER DETAILS

Code	Finish
VER.02.ES	Evershine Brass
VER.02.ESC	Evershine Chrome
VER.02.ESSCP	Evershine Satin Chrome



*subject to regular cleaning as instructed on the packaging.



GRIDLOCK®

Custom and Forte

Multipoint Lock

- British designed to the latest European specifications.
- Included in a security doorset tested to PAS 23 and PAS 24.
- Included in a fire resistant doorset tested to EN1634-1:2000 (Chilt RF02046A).
- Patented 20mm bolt throw with lift lever action and one turn of the key (Pat 0322874.9).
- Adjustable metal box keeps.
- Lacquered forend in gold or silver.
- Entry can be gained from either side of the door when unlocked.
- Dual followers to work with Custom and Forte lever furniture.
- Designed to operate with standard or ~~Sever~~ **Sever Secure** cylinders giving extra protection against cylinder attack.

GRIDLOCK®
C-Series



ORDER DETAILS

Code	Finish
MPL.GRID.C.GA	Lacquered Gold
MPL.GRID.C.SI	Lacquered Silver

GRIDLOCK®

Lever Furniture

Custom

- Solid brass patented design (Pat 0402804.9) *quick assemble* door furniture.
- Backplates can be fitted to the door in the factory, then the levers simply snap on later when required.
- Machine screw fixing from inside leaving invisible fixings from outside enhances security.
- External backplate incorporates cowl keyway to give extra protection against cylinder attack.
- Round bar lever ergonomically designed to suit lift up operation to throw dead bolts.

- Door furniture included in a security doorset tested to PAS 23 and PAS 24.
- Available in Evershine Polished Brass PVD or Evershine Polished and Satin Chrome PVD finishes.
- Guaranteed not to discolour for 25 years*.

Forte

Includes all of the features from the CUSTOM range plus:

- Combines the convenience and security features of both a night latch and a multi-point lock.
- Operational by Euro profile double cylinder, or cylinder and thumb turn.
- Lockable by a lift of the lever from either side, and one turn of the key or thumb turn from either side.
- Latch bolt withdrawn by handle from inside, but only by key from outside, also by extra turn of key or thumb turn from inside if required.
- Incorporates a snib function to hold back the latch bolt.



External handle featuring security cowl for defence against cylinder attack.

ORDER DETAILS	
Code	Finish
CUS.02.ES	Evershine Brass
CUS.02.ESC	Evershine Chrome
CUS.02.ESSCP	Evershine Satin Chrome



Internal handle detailing night latch facility.

ORDER DETAILS	
Code	Finish
FOR.02.ES	Evershine Brass
FOR.02.ESC	Evershine Chrome
FOR.02.ESSCP	Evershine Satin Chrome

35 x 30 (65mm) offset double cylinder required for 44mm thick doors.

*subject to regular cleaning as instructed on the packaging.



Intelligent UK Ltd.
(Trading as Intelligent Hardware)
Jubilee Business Park,
Copgrove, Harrogate HG3 3TB
Tel: 01423 340930
Fax: 01423 340923
Email: sales@intelligenthardware.co.uk
www.intelligenthardware.co.uk



INTELLIGENT BY DESIGN

